

JOHN GIBSON - CMAP - AMBULANCE
2nd West March STATION

3.34	Supply and lay 2.5mm Polysafe Standard PUR Safety Floor (Colour: 4560 - Storm Blue) vinyl flooring, including coved vinyl skirting (incl. cove formers and capping seals), transition strips, door stops, sealants and all accessories, cutting and forming to complete.				
		Flooring	22	m2	0.00
		Coved Skirting	20	Lm	0.00
	Miscellaneous				
3.35	Contractor to allow for installation of client supplied fixtures and fittings including - soap dispenser bracket, moisturiser lotion bracket, paper towel dispenser, paper roll dispenser and mop rack. Location of fixtures and fittings within sluice cupboard to be confirmed by CA.			Item	
3.36	On completion of works to this area, carry out a thorough clean ensuring that all surfaces are clean and dust free. Take photos upon completion.			Item	
3.37	Include for the supply and fixing of new wipeable vertical blinds to all windows include all tracks and accessories. Louvolite Vogue - 89mm vane. Type: Hand Operated Vertical Blind System. Ex-lite Fabric. 2000mm wide x 1200mm drop <i>Puma 934-Cocan</i>			Item	
			<i>CAMERON - VITON</i>		
			2	item	145.60
			<i>1850 x 1500</i>	<i>rid</i>	
			<i>1850 x 1500</i>	<i>lid</i>	
			<i>R4 2600 TOP</i>	<i>R4</i>	
4.00	Training Room				
4.01	Allow for the removal of all furniture, wall fixtures and fittings and store in adjacent office area. Allow for reinstatement on completion of the works.			Item	
4.02	Contractor to allow for the uplift of the existing floor finish and dispose of from site.			Item	
4.03	Contractor to allow for removal of existing timber skirting including removal of all nail fixings and dispose of from site.			Item	
4.04	Decoration Repair wall - patch repair plaster to external wall - see photo on AP(00)02 and make good to receive new finishes.			item	
4.05	Walls - Clean down, make good surfaces and apply one coat undercoat and two coats vinyl eggshell / satin paint, colour magnolia.		63	m2	0.00
4.06	Door - Prepare surfaces and apply one coat primer and two coats white gloss to the existing timber entrance door, including for frame and architraves. Allow for removal and replacement of ironmongery as required.		1	Nr.	
4.07	Window Sill - Prepare surfaces and apply one coat primer and two coats white gloss to existing decorated surfaces.		3	Item	
	Flooring Works				