

Customer NHSCT			Site. Fitters should b Inver 1 Holywell Hos		
Track Type	Spec	Location	Fitting Price	Price Uplift	Option List
Add to quotation Others to remove timber batons above window heads and Staff to remove Patients from room while work be					
		Ground floor			
Kestrel K2500		Room 72 Dining Room LR1			
Kestrel K2500		Room 72 Dining Room LR2			
Kestrel K2500		Room 72 Dining Room Bay LR3			
Kestrel K2500		Room 72 Dining Room Bay LR4			
Kestrel K2500		Room 72 Dining Room Bay LR5			
Kestrel K2500		Room 72 Dining Room LR6			
Pin hex anti-tamper security screws 1no every 150mm 40mm long					
Pin hex anti-tamper security screwdriver bits					
Fitting Instructions					
See special instructions column for fitting detail					
1.5 Mtr Sgl width tower with 6ft board					
Ladies Mental Health unit Staff to remove Patients from rooms while work being carried out and escort fitters if required. Tv					

Fitters curtains to have plastic hooks spaced evenly 16no per meter on track using all gliders on each track

Non magnetic Kestrel K2500 track. Face fix top of end brackets to glider hook 60mm. Top of profile to glider hook 40mm.

Trust spec track Kestrel K6200 track. Top of face fix magnet to glider hook 95mm. Top of top fix magnet to glider hook 45mm.

Kestrel K9500 track. Top of Face fix magnet to glider hook 115mm. Top of Top fix magnet to glider hook 65mm. Track profile

Date					
Key					
A					
B					
C					
D					
E					
F					
G					
H					
I					
J					
F3A					
IMS89					

--	--	--	--	--	--

be able to get tower straight into room via rear exit door

Contact

hospital Antrim

Siobhan McCann or Datta Doke or Paddi Gervin Tel. 9441 3349

Quantity	Width	Draw	Control side	Control Drop	Brackets	Fixing	Glider option	Supply and install Plastic hooks recommended by Yewdale for K2500 system	to track approx	Man power

being carried out and escort fitters if required.

1	1465	Bi part				Face	Option 3 heavy duty	Yes 16no per meter	3260	2 Men
1	1475	Bi part				Face	Option 3 heavy duty	Yes 16no per meter	3260	2 Men
1	1230	Bi part				Face	Option 3 heavy duty	Yes 16no per meter	3260	2 Men
1	1490	Bi part				Face	Option 3 heavy duty	Yes 16no per meter	3260	2 Men
1	1245	Bi part				Face	Option 3 heavy duty	Yes 16no per meter	3260	2 Men
1	1460	Bi part				Face	Option 3 heavy duty	Yes 16no per meter	3260	2 Men
?										
2										

Two Men at all times. No tools or equipment left unattended. See SMW7

--	--	--	--	--	--	--	--	--	--	--

Ext

Fitting
2 Men 0.75hr
2 Men 0.75hr
2 Men 0.75hr
2 Men 0.75hr
2 Men 0.75hr
2 Men 0.75hr

Parking, access



Special Instructions

Face fix top of track profile 115mm from ceiling grid which should make end brackets approx 95mm from ceiling grid D&P over lapping rev
Face fix top of track profile 115mm from ceiling grid which should make end brackets approx 95mm from ceiling grid D&P over lapping rev
Face fix top of track profile 115mm from ceiling grid which should make end brackets approx 95mm from ceiling grid D&P over lapping rev
Face fix top of track profile 115mm from ceiling grid which should make end brackets approx 95mm from ceiling grid D&P over lapping rev
Face fix top of track profile 115mm from ceiling grid which should make end brackets approx 95mm from ceiling grid D&P over lapping rev
Face fix top of track profile 115mm from ceiling grid which should make end brackets approx 95mm from ceiling grid D&P over lapping rev

s, tower 1.25hr



