

orks

Description of Works

	Description	Qty	Unit	Rate	£
	Supply and install Blinds to all perimeter windows; Yewdale Defiant roe fabric; as per specification within architects tender documents; colour to be agreed with architect; all as per architects drawings and specification		sum		
AC	2.20w x 2.70d 2nr				
	2.40w x 2.70d 8nr		sum		
AD	1.50w x 2.70d 3nr				
	0.40m x 2.70d 3nr				
	2.00m x 2.70d 2nr				
	0.50w x 2.70d 13nr		sum		
	1.00w x 2.70d 13nr				
	1.40w x 2.70d 5nr				
	0.90w x 2.70d 15nr				
	0.60w x 2.70d 11nr				
4.7	0.80w x 2.70d 2nr				
A	2.60w x 2.70d 2nr		sum		
	1.20w x 2.70d 3nr				
B	3.20w x 2.70d 2nr		sum		
C	Supply and install new Balustrade system to exposed edge of terrace seating area; 40 x 10 thick mild steel vertical bars, uprights, top and bottom rails with 50mm thick oak handrail checked over and screw fixed to top rail; uprights to be secured to floor/treads with matching circular plate fixing; all as per architects drawings and specifications (34.1)		sum		
D	Supply and install handrail to terrace seating area to match balustrade system; 50mm thick oak handrail checked over and screw fixed to fixing brackets; all as per architects drawings and specifications (34.2)		sum		
E	Contractor to allow for any other work deemed to be required to construct the design intent (Contractor is deemed to have included for all work identified within the drawings and specifications for completion of the works): [insert here]		sum		
	Carried to Collection; Stairs				0.00
4.8	MECHANICAL SERVICES				
A	Survey Carry out a detailed survey of the existing installations against the record drawings provided to check for discrepancies		sum		