

rainbow

blinds&interiors

61 Canyon Road, Excelsior Park
Wishaw, Lanarkshire ML2 0EG
01698 351888
01698 351999

contracts@rainbow-blinds.com

www.rainbow-blinds-and-interiors.co.uk

Insite Contracts Ltd
64 Coltness Street
Queenslie Industrial Estate
Glasgow
G33 4JD

09/01/2020

FAO Ms Victoria Millar

Ref: Titan, Eurocentral, Motherwell

Dear Ms Millar

Further to our recent visit to the above site, we have pleasure in submitting our tender sum for the supply and installation of 21 nr vertical blinds. The blinds shall be manufactured in the Vogue headrail system with dual control operation with the controls fitted to comply with current blind safety regulations. The blinds louveres shall be manufactured in the fabric of your clients choosing from our C range of FR materials.

Tender Sum £4,046.00 less 2.5% MCD plus VAT

We hope the above cost meets with your approval and look forward to hearing from you at your earliest convenience.

Assuring you of our best service at all times.

Yours Sincerely

Stephen Boyce
Contracts Manager

C+40%

○ Titan (Can't access some rooms.)

| | | | |
|-----------------------------|---------------------|--------|----------|
| 2740 × 1345 | × 1 × 19 | 193.20 | £3670.80 |
| 3630 × 1700 1345 | × 1 | 249.20 | |
| 1700 × 1345 | × 1 | 126.00 | |

£4046.00 less 2.5% MCD + VAT.

| SCHEDULE OF WORKS | | Unit | Qty | Rate | Cost |
|--|---|-------------|------------|-------------|------------------|
| Titan, 7 Dovecote Road, Eurocentral, Motherwell ML1 4XN | | | | | |
| 11.00 | MISCELLANEOUS WORKS | | | | |
| | <u>Externally:</u> | | | | |
| 11.01 | Remove the existing capping piece to the curtain walling at the main entrance (1 no length has been screw fixed in place). Supply materials and install new capping piece correctly including any adjustments required to the pressure plates etc; all to complete. | Sum | | | |
| 11.02 | Contractor to allow for heavy duty protection to be provided to the site boundaries to avoid any unwanted/tersspassing until such time as the fencing works have completed. Temporary concrete bollards or similar to be provided. (Note: Heras fencing will not suffice). | Sum | | | |
| 11.03 | Remove all damaged and/or otherwise defective kerb flag stones and replace to match existing. Including for fully breaking out existing and thereafter allowing for rebedding new matching flagstones in mortar to match existing levels; all to complete. Allow a Provisional Quantity of 10lm for costing purposes. | 10 | lm (PQ) | | |
| 11.04 | Overhaul the main double entrance doors into the building and ensure left in full working order. Understand that new transom closer and drive arm required and flush bolts are broken/defective. | Sum | | | |
| 11.05 | Overhaul the pass door to the first floor corridor and ensure in full working order. | Sum | | | |
| 11.06 | Overhaul all blinds to the upper floor kitchen area, offices etc. Ensure left in full working order. | Sum | | | |
| 11.07 | Allow for a full specialist clean of the area above the ancillary office area to remove all contamination and bord guano fouling throughout. | Sum | | | |
| 11.08 | Allow for completing the works to the lift providing access to upper floor offices. Kone quote and service repair propsoals identified works required. Copy provided with tender documentation, dated 19 August 2019, ref: T-0003243183 ver 1. | Sum | | | |
| 11.09 | Allow for clearing out and repairing the concrete slot linear drain to west elevation and to opposite side of yard. Ensure fully functioning upon completion. | Sum | | | |
| 11.10 | PS for any repairs required to the dock levellers and roller doors. | PS | | | £2,500.00 |
| 11.11 | PS for any works required to repair/overhaul the electrical car charging points. | PS | | | £2,500.00 |
| AMOUNT OF MISCELLANEOUS WORKS TO COLLECTION | | | | | £5,000.00 |