

WARD 17 ANTI-LIGATURE ALTERATIONS
ST JOHNS HOSPITAL, LIVINGSTON
PRICING SCHEDULE - PHASE 1



Ref	Description	Quantity	Unit	Rate	Amount (£)
	SPECIAL PURPOSE FITTINGS & FURNISHINGS				
A	Radiator housings; Large; ref: M1; contour deepclean anti-ligature guard; wall mounted; radiused corners and gradient top; White powder coated; 2mm thick steel; as schedule 2324/SCH01 B; complete (approx quantity 3Nr)		Item		
B	Radiator housings; Small; ref: M1; contour deepclean anti-ligature guard; wall mounted; radiused corners and gradient top; White powder coated; 2mm thick steel; as schedule 2324/SCH01 B; complete (approx quantity 1Nr)		Item		
C	Bump Rails; ref: M2; CS Acrovyn 4000 HRB4C (AL); 140mm high; 76mm stand off; anti-ligature rail ; continous bracket; as schedule 2324/SCH01 B; complete (approx quantity 36m)		Item		
D	Bedside cupboard; ref: M3; to match existing; 18mm melamine chipboard; anti-ligature hinges; radiused corners; as schedule 2324/SCH01 B; complete (approx quantity 7Nr)		Item		
E	Door hold open; ref: M5; maglocks 2No. per door); finishes made good accordigly; as schedule 2324/SCH01 B; complete (approx quantity 1Nr)		Item		
F	Fire hose housing; ref: M6; to existing; infill 600 x 600mm; 12mm plywood; 12mm wallboard; as schedule 2324/SCH01 B; complete		Item		
G	Worktops; to Untility rooms; ref: M8; including new under panels, sinks and taps; as schedule 2324/SCH01 B; complete		Item		
H	Under panels; to Servery room; ref: M9; under existing worktops and sinks; as schedule 2324/SCH01 B; complete		Item		
I	TV Cabinet; ref: M11; lockable front and base unit; fixed to wall; concealed cables; as schedule 2324/SCH01 B; complete (approx quantity 1Nr)		Item		
J	Shelving unit; anti-ligature; fixed to wall; as schedule 2324/SCH01 B; complete (approx quantity 3Nr)		Item		
K	Curtin rail track; Goldcrest; anti-ligature; fixed to ceiling; complete (approx quantity 20m)		Item	1,605.00	1,605.00
			To Collection		1605.00

WARD 17 ANTI-LIGATURE ALTERATIONS
ST JOHNS HOSPITAL, LIVINGSTON
PRICING SCHEDULE - PHASE 2



Ref	Description	Quantity	Unit	Rate	Amount (£)
A	Bedside cupboard; ref: M3; to match existing; 18mm melamine chipboard; anti-ligature hinges; radiused corners; as schedule 2324/SCH01 B; complete (approx quantity 8Nr)		Item		
B	Door hold open; ref: M5; maglocks 2No. per door); finishes made good accordingly; as schedule 2324/SCH01 B; complete (approx quantity 1Nr)		Item		
C	Fire hose housing; ref: M6; to existing; infill 600 x 600mm; 12mm plywood; 12mm wallboard; as schedule 2324/SCH01 B; complete		Item		
D	TV Cabinet; ref: M11; lockable front and base unit; fixed to wall; concealed cables; as schedule 2324/SCH01 B; complete (approx quantity 1Nr)		Item		
E	Shelving unit; anti-ligature; fixed to wall; as schedule 2324/SCH01 B; complete (approx quantity 3Nr)		Item		
F	Curtin rail track; Goldcrest; anti-ligature; fixed to ceiling; complete (approx quantity 23m)		Item	1,770.00	1,770.00
Sanitary Appliances					
G	Bedroom basin; ref: S1; wall mounted; concealed water nozzles; touch buttons; electronic water controls ; include for all fittings etc; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 3Nr)		Item		
H	WC; ref: S2; WC pan and part height IPS; touch buttons; electronic water controls ; include for all fittings etc; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 2Nr)		Item		
I	Basin; ref: S3; wall mounted; concealed water nozzles; touch buttons; electronic water controls ; include for all fittings etc; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 4Nr)		Item		
J	Shower; ref: S4; Horne T105ALR; anti-ligature head and controls; include for all fittings etc; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 2Nr)		Item		
K	En-suite package; ref: S6; including IPS to WC and basin, tower shower, basin, WC pan; touch control; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 2Nr)		Item		
				To Collection	1770.00

WARD 17 ANTI-LIGATURE ALTERATIONS
ST JOHNS HOSPITAL, LIVINGSTON
PRICING SCHEDULE - PHASE 3



Ref	Description	Quantity	Unit	Rate	Amount (£)
A	Shelving unit; anti-ligature; fixed to wall; as schedule 2324/SCH01 B; complete (approx quantity 3Nr)		Item		
B	Curtin rail track; Goldcrest; anti-ligature; fixed to ceiling; complete (approx quantity 23m)		Item	1,770.00	1,770.00
Sanitary Appliances					
C	Bedroom basin; ref: S1; wall mounted; concealed water nozzles; touch buttons; electronic water controls ; include for all fittings etc; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 3Nr)		Item		
D	WC; ref: S2; WC pan and part height IPS; touch buttons; electronic water controls ; include for all fittings etc; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 1Nr)		Item		
E	Basin; ref: S3; wall mounted; concealed water nozzles; touch buttons; electronic water controls ; include for all fittings etc; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 2Nr)		Item		
F	Shower; ref: S4; Horne T105ALR; anti-ligature head and controls; include for all fittings etc; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 1Nr)		Item		
G	En-suite package; ref: S6; including IPS to WC and basin, tower shower, basin, WC pan; touch control; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 2Nr)		Item		
H	Anti-ligature IPS to WC and basin, half height to wall; sloping top; solid grade laminate panels as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 2Nr)		Item		
I	Commissioning; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete		Item		
J	Toilet roll holder; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 1Nr)		Item		
K	Mirrors; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 5Nr)		Item		
L	Hand Towel dispenser; as drawings 2324/AG 02 and Schedule of Works 2324/SCH 01 B complete (approx quantity 5Nr)		Item		
M	Ventilation grilles; anti-ligature; complete (approx quantity 8Nr)		Item		
				To Collection	1770.00

WARD 17 ANTI-LIGATURE ALTERATIONS
ST JOHNS HOSPITAL, LIVINGSTON
PRICING SCHEDULE - PHASE 4



Ref	Description	Quantity	Unit	Rate	Amount (£)
	Ceiling Finishes				
A	Suspended ceiling; Type C1; Armstrong S-Clip F System; 600x600mm bevel edged metal ceiling tile; 0.5mm thick; colour RAL 9010 white; concealed grid; including ceiling channels, insulation, edge trims etc; as Drawings 2324/AG03 A and Schedule of Works 2324/SCH 01B; complete (approx quantity 24m2)		Item		
B	Suspended ceiling; Type C2; British Gypsum ref Casoline MF; concealed metal frame; including ceiling channels, insulation, edge trims etc; tape and fill; as Drawings 2324/AG03 A and Schedule of Works 2324/SCH 01B; complete (approx quantity 90m2)		Item		
C	Paint to ceiling; 1 coat eggshell paint; colour TBC; including all necessary preparation; as Drawings 2324/AG03 A and Schedule of Works 2324/SCH 01B; complete (approx quantity 98m2)		Item		
D	Access hatches; Profilex bespoke anti ligature; as Drawings 2324/AG03; complete (approx quantity 5Nr)		Item		
	SPECIAL PURPOSE FITTINGS & FURNISHINGS				
E	Radiator housings; Large; ref: M1; contour deepclean anti-ligature guard; wall mounted; radiussed corners and gradient top; White powder coated; 2mm thick steel; as schedule 2324/SCH01 B; complete (approx quantity 1Nr)		Item		
F	Radiator housings; Small; ref: M1; contour deepclean anti-ligature guard; wall mounted; radiussed corners and gradient top; White powder coated; 2mm thick steel; as schedule 2324/SCH01 B; complete (approx quantity 2Nr)		Item		
G	Bump Rails; ref: M2; CS Acrovyn 4000 HRB4C (AL); 140mm high; 76mm stand off; anti-ligature rail ; continous bracket; as schedule 2324/SCH01 B; complete (approx quantity 6m)		Item		
H	Bedside cupboard; ref: M3; to match existing; 18mm melamine chipboard; anti-ligature hinges; radiussed corners; as schedule 2324/SCH01 B; complete (approx quantity 8Nr)		Item		
I	Fire hose housing; ref: M6; to existing; infill 600 x 600mm; 12mm plywood; 12mm wallboard; as schedule 2324/SCH01 B; complete		Item		
J	Worktops; to Utility rooms; ref: M8; including new under panels, sinks and taps; as schedule 2324/SCH01 B; complete		Item		
K	Curtin rail track; Goldcrest; anti-ligature; fixed to ceiling; complete (approx quantity 23m)		Item	1,770.00	1,770.00
			To Collection		1770.00