



<b>3.00 JOINER WORKS</b>				
3.01	Supply all necessary plant, material and labour required to install new Magnet or Howden style kitchen to staff welfare areas to include for specification as follows:-  a) 1000mm base units b) 1000mm wall units c) Plinth to match kitchen system d) End panels e) End caps f) Laminate Worktop  Contractor to allow for all liaison with Client to arrange the position and for worktop cut outs to be incorporated.	2 2 Sum Sum Sum Sum	No. No.	
3.02	Supply all necessary plant, labour and materials required to install new light-coloured roller blinds supplied by Apollo blinds or equal and approved to all windows. Include for incorporating CalMac logo within blind to each window as directed by CA. All windows to be site sized.	No	11	2144.00
3.03	Supply all necessary plant, labour and materials required to supply and install fixtures and fittings within sanitary accommodation as follows: (Specification to be stainless steel- supplied by <b>Dolphin Solutions</b> )  a) Wall mounted mirrors 1500mm x 900mm (to areas as instructed on site by Contract Administrator. Site sizes to be confirmed). b) Soap dispensers (to areas as instructed on site by Contract Administrator). c) Toilet roll holders (to areas as instructed on site by Contract Administrator).	No No No	2 2 2	
3.04	Supply all necessary plant, labour and materials required to supply and install new sheet 'Perspex' or similar and approved splashback to walls below new hand driers. Colour to be white. All with perimeter trims to the sanitary accommodation. Size to be approximately 600mm (w) from underside of drier position to floor/skirting level. Contractor to include for all levelling as required prior to installation to ensure substrate flush ready to receive splashback.	No	2	
3.05	Supply all necessary plant, materials and labour required to carry out all required alterations as required and install new UPVC fascia panels in colour white to all areas previously removed. Contractor responsible for site sizing depth as required. Note fascia to be installed at eaves and part height to the full building perimeter.	Linm	70	
<b>AMOUNT OF JOINER WORKS TO COLLECTION</b>				<b>2144.00</b>