

P21: Ironmongery				
Preamble: to be read in conjunction with Wellwood Leslie Door Schedule and Architectural Specification				
<u>Existing Doors</u>				
Replace all existing door handles with new: (Door Handle Company) Atlantic Door Handles Old English Radius Wrexham, Matt Antique Brass - ROE-142 MAB.				
5.18	Complete;	27	nr	
<u>New Doors</u>				
Replace all existing door handles with new: (Door Handle Company) Atlantic Door Handles Old English Radius Wrexham, Matt Antique Brass - ROE-142 MAB. Allow for 3no. Ball bearing hinges, thumb locks all finished to match surrounding lever handles.				
5.19	Complete;	11	nr	
P20: Unframed Isolated Trims / Skirtings / Sundry Items				
<u>Skirtings</u>				
Supply and fit new MDF pencil round skirting to match existing.				
5.20	Basement file storage partitions, complete;	10.6	lm	
5.21	Second Floor door infill, complete;	1.7	lm	
5.22	Basement toilet partitions, complete;	10.4	lm	
5.23	Basement kitchen door infill, complete;	1.8	lm	
5.24	Ground floor toilet partitions, complete;	7.4	lm	
5.25	Second floor toilets partitions, complete;	10.4	lm	
<u>Wall Timber Framework</u>				
To be read in conjunction with Wellwood Leslie drawings: 0201 and 0202				
Preamble: <u>Fabrication drawings to be issued for approval by client prior to installation.</u>				
Supply and fit new 70mm wide timber new wood frames forming timber panelling effect. To match existing picture rails and the like, ready for decoration.				
5.26	Basement Floor, complete;	1	sum	
5.27	Ground Floor, complete;	1	sum	
<u>Window Blinds</u>				
Supply and install roller blinds with high definition company logo to first and second floor windows facing Walker Street.				
5.28	Complete;	14	nr	Various 2069.80
Supply and install curtains - SilentGliss (Colour: Light warm grey);				
5.29	Ground Floor Boardroom, complete;	1	sum	2751.00 2751.00
5.30	Ground Floor Rear Room, complete;	1	sum	1375.50 1375.50
				6196.30