

# Tender Document

Client Name: NHS Tayside

Project Title: Proposed Alterations to Wards 4 & 5, Royal Victoria Hospital

Project Nr: DQ3969



Bill Nr 3 Alteration Works

Measured Works

Item	Description	Quantity	Unit	Rate	Extension
				b/f	
	<u>Smoothing primer: "Ball Stoppap 131"</u>				
	2-3 work to existing floors on concrete base; level and to slight falls only; not exceeding 15 degrees from horizontal; laid in accordance with manufacturers recommendations				
A	Width exceeding 300; float finish	3	m2		
	<u>Smoothing underlayment "Ball Stoppap 200"</u>				
	2-3 work to existing floors on concrete base; level and to slight falls only; not exceeding 15 degrees from horizontal; laid in accordance with manufacturers recommendations				
B	Width exceeding 300; float finish	3	m2		
	<u>Liquid damp proof membrane: "Contractors Choice"</u>				
	To existing floors on concrete base				
C	Width exceeding 300; bonded and applied in accordance with manufacturers recommendations	3	m2		
	<u>Non slip vinyl flooring "Altro Aquarius"; colour "Blue Penguin"; fixing with adhesive; hot seam welding with complimentary coloured rod; washing on completion with cleaner recommended by the flooring manufacturer; as Specification Clause M50/151</u>				
	2 work to existing floors on concrete base; to falls and crossfalls				
D	Width exceeding 300	3	m2		
E	Extra; neat flush joint against existing flooring	3	m		
	2 work to skirtings on existing plaster base; coved, including cove former and capping seal				
F	Height 100mm; vertical	3	m		
	<b><u>N FURNITURE/EQUIPMENT</u></b>				
	<b><u>N10 General fixtures/furnishings/equipment</u></b>				
	<u>Cubicle rails and accessories: "Silent Gliss Ltd"; mainly in aluminium and nylon; white powder coated finish; as Specification Clause N13/493</u>				
	6100 curtain rail system <b>F1-042</b>				
G	Track; profile 6101; complete with vertical hangers 6190 at recommended centres	5.85	m	28.90	169.07
H	Wall supports; Reference 6609	4	Nr	5.20	20.80
				c/f	189.87

# Tender Document

Client Name: NHS Tayside

Project Title: Proposed Alterations to Wards 4 & 5, Royal Victoria Hospital

Project Nr: DQ3969



Bill Nr 3 Alteration Works  
Measured Works

Item	Description	Quantity	Unit	Rate	Extension
	f1-042			b/f	
A	Dust cover; Reference 6110	5.85	M	2.08	12.17
B	Glider hooks; Reference 6147 (Provisional)	59	Nr	0.40	23.60
	<u>Fit only the following "Group 2" items</u>				
	Take delivery from the Employer and fit only the following:-				
C	Shower curtain	1	Nr		
	<u>N13 Sanitary appliances/fitings</u>				
	<u>Appliances: "Blucher Uk Ltd"</u>				
	Stainless steel floor gulley; set within existing concrete floor				
D	110 Nominal size	1	Nr		
	<u>P BUILDING FABRIC SUNDRIES</u>				
	<u>P31 Holes/Chases/Covers/Support for services</u>				
	<u>General Builder's Work</u>				
	Cutting or forming mortices, sinkings in the structure				
E	Not exceeding 110 nominal diameter; approx 150mm thick beam / block flooring; complete	1	Nr		
	<u>Accessories</u>				
	Fire collar; to provide 60 minutes fire resistane; within existing 150 thick concrete flooring				
F	110 nominal size; sealant as required	1	Nr		
<b>AMOUNT OF WORK SECTION TO BILL NR 3 COLLECTION</b>				<b>£</b>	<b>35.77</b>

# Tender Document

Client Name: NHS Tayside

Project Title: Proposed Alterations to Wards 4 & 5, Royal Victoria Hospital

Project Nr: DQ3969



Bill Nr 3 Alteration Works

Measured Works

Item	Description	Quantity	Unit	Rate	Extension
				b/f	
A	To existing floors on concrete base  Width exceeding 300; bonded and applied in accordance with manufacturers recommendations	3	m2		
	<u>Non slip vinyl flooring "Altro Aquarius"; colour to be agreed; fixing with adhesive; hot seam welding with complimentary coloured rod; washing on completion with cleaner recommended by the flooring manufacturer; as Specification Clause M50/151</u>				
B	2 work to existing floors on concrete base; To falls and crossfalls  Width exceeding 300	3	m2		
C	Extra; neat flush joint against existing flooring	3	m		
D	2 work to skirtings on existing plaster base; coved, including cove former and capping seal  Height 100mm; vertical	3	m		
	<b><u>N FURNITURE/EQUIPMENT</u></b>				
	<b><u>N10 General fixtures/furnishings/equipment</u></b>				
	<u>Cubicle rails and accessories: "Silent Gliss Ltd"; mainly in aluminium and nylon; white powder coated finish; As Specification Clause N13/493</u>				
E	6100 curtain rail system <i>F1-052</i>  Track; profile 6101; complete with vertical hangers 6190 at recommended centres	2.4	m	42.42	101.81
F	Wall supports; Reference 6609	2	Nr	5.20	10.40
G	Dust cover; Reference 6110	2.4	M	2.08	4.99
H	Glider hooks; Reference 6147 (Provisional)	24	Nr	0.40	9.60
	<u>Mirrors: Class C safety glass with aluminium foil backing</u>				
I	6 thick; fixing to IPS unit with chromium plated dome top wood screws; polythene sleeves and washers  300 x 400; edges smoothed and polished	1	Nr		
	<u>Fit only the following "Group 2" items</u>				
J	Take delivery from the Employer and fit only the following:-  Shower curtain	1	Nr		
				c/f	126.80

# Tender Document

Client Name: NHS Tayside

Project Title: Proposed Alterations to Wards 4 & 5, Royal Victoria Hospital

Project Nr: DQ3969



Bill Nr 3 Alteration Works

Measured Works

Item	Description	Quantity	Unit	Rate	Extension
				b/f	
A	Width exceeding 300; bonded and applied in accordance with manufacturers recommendations  <u>Non slip vinyl flooring "Altro Aquarius"; colour "Blue Penguin"; fixing with adhesive; hot seam welding with complimentary coloured rod; washing on completion with cleaner recommended by the flooring manufacturer; as Specification Clause M50/151</u>  2 work to existing floors on concrete base; to falls and crossfalls	3	m2		
B	Width exceeding 300	3	m2		
C	Extra; neat flush joint against existing flooring  2 work to skirtings on existing plaster base; coved, including cove former and capping seal	3	m		
D	Height 100mm; vertical  <u>N FURNITURE/EQUIPMENT</u>  <u>N10 General fixtures/furnishings/equipment</u>  <u>Cubicle rails and accessories: "Silent Gliss Ltd"; mainly in aluminium and nylon; white powder coated finish; As Specification Clause N13/493</u>  6100 curtain rail system <i>F1-074</i>	3	m		
E	Track; profile 6101; complete with vertical hangers 6190 at recommended centres	3.7	m	49.23	182.15
F	Wall supports; Reference 6609	2	Nr	5.20	10.40
G	Dust cover; Reference 6110	3.7	M	2.08	7.70
H	Glider hooks; Reference 6147 (Provisional)  <u>Fit only the following "Group 2" items</u>  Take delivery from the Employer and fit only the following:-	37	Nr	0.40	14.80
I	Shower curtain  <u>N13 Sanitary appliances/fittings</u>  <u>Appliances "Euro Showers"; As Specification Clause N13/376</u>	1	Nr		
J	Shower head; Reference "Eurospray 84660"	1	Nr		
K	Shower hose; Reference "Eurospray 52820"	1	Nr		
				c/f	175.05

# Tender Document

Client Name: NHS Tayside

Project Title: Proposed Alterations to Wards 4 & 5, Royal Victoria Hospital

Project Nr: DQ3969



Bill Nr 3 Alteration Works  
Measured Works

Item	Description	Quantity	Unit	Rate	Extension
				b/f	
A	2-3 work to existing floors on concrete base; level and to slight falls only; not exceeding 15 degrees from horizontal; laid in accordance with manufacturers recommendations Width exceeding 300; float finish <u>Smoothing underlayment "Ball Stopgap 200"</u>	3	m2		
B	2-3 work to existing floors on concrete base; level and to slight falls only; not exceeding 15 degrees from horizontal; laid in accordance with manufacturers recommendations Width exceeding 300; float finish <u>Liquid damp proof membrane: "Contractors Choice"</u>	3	m2		
C	To existing floors on concrete base Width exceeding 300; bonded and applied in accordance with manufacturers recommendations <u>Non slip vinyl flooring "Altro Aquarius"; colour "Blue Penguin"; fixing with adhesive; hot seam welding with complimentary coloured rod; washing on completion with cleaner recommended by the flooring manufacturer. as Specification Clause M50/151</u>	3	m2		
D	2 work to to existing floors on concrete base; to falls and crossfalls Width exceeding 300	3	m2		
E	2 work to skirtings on existing plaster base; coved, including cove former and capping seal Height 100mm; vertical	3	m		
	<b><u>N FURNITURE/EQUIPMENT</u></b> <b><u>N10 General fixtures/furnishings/equipment</u></b>  <u>Cubicle rails and accessories: "Silent Gliss Ltd"; mainly in aluminium and nylon; white powder coated finish; As Specification Clause N13/493</u>  6100 curtain rail system <i>F1-089</i>				
F	Track; profile 6101; complete with vertical hangers 6190 at recommended centres	5.3	m	30.85	163.51
G	Wall supports; Reference 6609	4	Nr	5.20	20.80
H	Dust cover; Reference 6110	5.3	Nr	2.08	11.02
I	Glider hooks; Reference 6147 (Provisional)	53	Nr	0.40	21.20
				c/f	216.53

# Tender Document

Client Name: NHS Tayside

Project Title: Proposed Alterations to Wards 4 & 5, Royal Victoria Hospital

Project Nr: DQ3969



Bill Nr 3 Alteration Works

Measured Works

Item	Description	Quantity	Unit	Rate	Extension
	<b>COLLECTION</b>				
	BAY 4 STORE				
	ROOM F1-042				225.64
	ROOM F1-043				
	ROOM F1-050				
	ROOM F1-052				
	ROOM F1-055				126.80
	LOUNGE				
	ROOM F1-074				175.05
	ROOM F1-077				
	ROOM F1-089				216.53
<b>TOTAL FOR BILL NR 3 TO SUMMARY</b>				£	744.02