

						£	p
320013T	A	<p>Worktop; Solid grade Trespa Toplab worktop, minimum 16mm thick, complete with 50mm moulded rear upstand; all exposed edges to be polish sanded and have chamfered, cushion or radius edges; all exposed corners to have a radius of 30mm</p> <p>approximately 750mm wide</p> <p><u>Supply and install spur shelving; contractors choice of manufacturer; proposals to be submitted for approval; complete with all vertical wall brackets fixed at approved centres and adjustable shelving to suit clients requirements; complete with all brackets, fitments, fittings, supports and accessories; to be installed in strict accordance with the manufacturers printed instructions</u></p>	6	m			
3200165	B	<p>Spur Shelving; wall mounted (Provisional)</p> <p>approximately 300mm wide; comprising 3 no tiers</p> <p><u>Supply and install roller blind as manufactured by Silent Gliss or equal and approved; SC series roller system or equal and approved; monocontrol chain and rotation elements; White colour, fabric to be treated with approved fire retarding system; Manual operations; Include wall fixings, brackets, supports, chain, fittings, clamps, end covers and accessories etc; to be installed in strict accordance with the manufacturers printed instructions; all in accordance with specification clause N10/240</u></p>	6	m			
3200170	C	<p>Roller blinds; generally</p> <p>to suit window approximately 970mm wide x 600mm blind drop</p>	7	no	177.32		1241.24
3200172	D	<p>to suit window approximately 750mm wide x 600mm blind drop</p>	4	no	168.17		672.68
To Collection £							1913.92

					£	p
		<p><u>Supply and install roller blind as manufactured by Silent Gliss or equal and approved; Reference 4510 chain operated dim-out roller blind system or equal and approved; fully assembled with 55mm cassette, side profile reference 4513/14 to allow fitting outside of recess and right hand side chain operation; side and plastic components to be white colour and the fabric is to be chosen from the Silent Gliss range, fabric to be treated with approved fire retarding system; Manual operations; Include wall fixings, brackets, supports, chain, fittings, clamps, end covers and accessories etc; to be installed in strict accordance with the manufacturers printed instructions; all in accordance with specification clause N10/241</u></p>				
3200176	A	<p>Dim-out roller blinds</p> <p>to suit window approximately 970mm wide x 600mm blind drop</p>	2	no	196.25	392.50
		<p><u>Take delivery and install the following; (supplied by Client); include for all brackets, fixings, fittings, supports, accessories, etc</u></p>				
		<p>Wall mounted</p>				
3200A19	B	<p>monitor brackets; based on 2 no per monitor (brackets measured individually)</p>	8	no		
3200A1A	C	<p>clock</p>	3	no		
3200A1C	D	<p>1200 x 900 whiteboard</p>	5	no		
		<p><u>Door signage; as manufactured by Signcraft or equal and approved; Product Aluminium plate standard NHS signage; to HTM; be determined by client; fixed using countersunk screw/ adhesive fixed as advised by manufacturer; all in accordance with the specification</u></p>				
		<p>Door mounted</p>				
3200A4T	E	<p>NHS GG&C Room Number Signage (Provisional)</p>	3	no		
					To Collection £	392.50

						£	p
					Collection		
					Amount of Page 15 / 1		0.00
					Amount of Page 15 / 2		0.00
					Amount of Page 15 / 3		0.00
					Amount of Page 15 / 4		1913.92
					Amount of Page 15 / 5		392.50
					Amount of Page 15 / 6		0.00

To Summary £ 2306.42