

5.06	Contractor to allow for the necessary boxing out of the walls containing the pipework and drainage. Thereafter allow for lining the walls to approximately 1/3 height using tonged and groove timber with timber capping piece. Contractor to allow for the provision of access hatches for stop cocks and water meters. All labours and works complete	Item	
<b>MANAGERS OFFICE</b>			
5.07	Allow for provision of new acoustic drop barrier to base of access door to managers office. All labours and works complete.	Item	
<b>RECEPTION AREA</b>			
5.08	Allow for the provision of a free standing (but fixed back to the reception desk) spray finished MDF modesty panel to be full height and thickness of circa 100mm with a spray finished MDF counter top to convert the existing desk into more of a reception based desk and assist with concealing the top of the desk.	Item	
<b>BLINDS</b>			
5.09	Contractor to allow for the provision of a roller blind above the glazed dead light panel (allow for self close action to remove need to string near entrance door) Blind to have ability to be pulled to GFL at night. All labours and works complete	Item	327.60
5.10	Contractor to allow for the provision of new slats for the existing blinds within the front office to match the colour and fabric of the remaining blinds within the accommodation. All labours and works complete	Item	515.76
<i>Joinery - to Collection</i>			843.36