

rainbow blinds&fabrics

61 Canyon Road, Excelsior Park
Wishaw, Lanarkshire ML2 0ER
01698 351888
01698 351999

contracts@rainbow-blinds.com

www.rainbow-blinds-and-interiors.co.uk

18th July, 2019

Worksmart Contracts,
60 Bank Street,
Kilmarnock.
KA1 1ER

For the attention of Cameron Maudsley:

Visit Scotland – 90 St.Vincent Street:

Dear sir,

We thank you for your valued enquiry in respect of the following and have much pleasure in submitting our quotation for your approval.

Supply & install 21 no. system 32 roller blinds in the Group B range of FR Dimout material with 13 no. printed with **Visit Scotland** Logos.

Supply & install silver 80c solar reflective film to comms store window.

Price £2730.38

Less 2 ½% MCD

All prices are exclusive of Vat.

Yours faithfully,

Stephen Boyce,

22nd July

Allison Swankie

From: Sales
Sent: 12 July 2019 10:49
To: Allison Swankie
Subject: FW: VisitScotland - 90 St. Vincent Street
Attachments: 90 St Vincent Street Drawings.zip; Schedule of works - VisitScotland 90 St Vincent Street.pdf

IS THIS FOR YOU??

XXX

From: Cameron Maudsley <cameron.maudsley@worksmartcontracts.co.uk>
Sent: 12 July 2019 10:21
Subject: VisitScotland - 90 St. Vincent Street

Good Morning,

Please find attached tender documents for pricing the supply and installation of Blind works at the above named project.

Note that we require costs back by Monday 22nd July.

Should you have any queries, or decline to tender, please let me know as soon as possible.

Many thanks.

Kind regards

Cameron Maudsley Trainee Quantity Surveyor
t. +44 (0)1563 535 511
m. +44 (0)749 468 0599
e. cameron.maudsley@worksmartcontracts.co.uk



makeitworksmart.co.uk



HEAD OFFICE First Floor | 60 Bank Street | Kilmarnock KA1 1ER

KILMARNOCK EDINBURGH LONDON MANCHESTER

Notice of Confidentiality The information contained in this email is intended for the named recipients only. It may contain privileged and confidential information and if you are not an intended recipient you must not copy, distribute or take any action in reliance on it. If you have received this message in error please notify us immediately by email to enquiries@worksmartcontracts.co.uk Recipients must understand that conclusions, opinions and other information

DESCRIPTION OF WORKS

		Unit	Qty	Rate	Cost
	New Door Type B - Supply materials and undertake works to install new veneered solid core timbers door leading into newly formed door openings. Door finishes to match the existing entrance and fire exit doors as closely as possible. Door size to be approx. 926mm wide by 2040mm high and 44mm thick, door ironmongery to include overhead closer, kickplates, 1.5 pairs butt hinges, lever lock/latch handle with key operated mortice lock set, exact specification to be agreed with Contract Administrator, contractor to be responsible for measurement of opening of doors; Type Door				
3.20	a) Store Room	SUM			
3.21	b) Data / IT Room	SUM			
3.22	Supply and fit new door facings to match existing main entrance and fire exit doors to match 70mm x 12mm double pencil around the facings and plinth blocks to go sides of door formed in MDF, contractor to include for all necessary mitring of corners, cutting and wastage to complete	SUM			
3.23	Supply materials and create new pencil rounded MF skirting to base of all newly created walls, indicative size of skirting 70mm x 15mm thick, however specific size of existing skirting to be taken by contractor and materials to be provided to match. Contractor to include for all necessary mitred joints, cutting and wastage to complete.	SUM			
3.24	Reinstate all previously set aside timber skirtings upon installation of new partitions; include for all cutting and wastage to accommodate new layout and prepare ready for decoration.	SUM			
3.25	Supply and fit new roller window blinds over all existing window openings in colour branded VisitScotland Purple complete with VisitScotland logo manifestation on each window blind. Note that multiple blinds may be required for enlarged openings to the breakout area and to rear open plan office areas.	SUM	21nr	various	£2,565.38
3.26	<u>New wall mounted cupboard:</u> Supply and fit new wall mounted double cupboard to the existing tea area to match existing fittings.	SUM			
3.27	<u>Breakout Area Breakfast Bar:</u> Supply materials and undertake works to install new bull nose edge to 38mm thick laminate worktop along the width of the window to the newly formed Breakout area (approximate width of window opening 4.2m) worktop to be 600mm deep. Contractor to allow for charcoal colour although final decision and colour to be agreed with Contract Administrator prior to ordering; include for provision of fitting new worktop sockets to the breakfast bar; include for supporting polished steel rods.	SUM			

DESCRIPTION OF WORKS



		Unit	Qty	Rate	Cost
7:00	Miscellaneous Works				
7.01	Allow for full sparkle clean upon completion of the works to all affected areas.	SUM			
7.02	Supply and apply new solar reflective film to the windows serving the Comms store, include for all cutting and wastage.	SUM	1nr	165.00	165.00
AMOUNT OF MISCELLANEOUS WORKS TO COLLECTION					£165.00