

RC1129

# rainbow blinds&fabrics

61 Canyon Road, Excelsior Park  
Wishaw, Lanarkshire ML2 0ER  
01698 351888  
01698 351999

[contracts@rainbow-blinds.com](mailto:contracts@rainbow-blinds.com)

[www.rainbow-blinds-and-interiors.co.uk](http://www.rainbow-blinds-and-interiors.co.uk)

1<sup>st</sup> August, 2019.

BSL Interiors Ltd,  
Old School,  
189 Old Shettleston Road,  
Glasgow  
G32 7HN.

For the attention of: Keiran Nixon.

**Ref: WCS Greenock:**

Dear Sir,

We thank you for your valued enquiry in respect of the following and have much pleasure in submitting our quotation for your approval.

To supply and install system 40 roller blinds complete with control guards fitted to comply with current blind safety regulations, the blinds shall be covered in the carnival china white blackout material with the louvolite teardrop bottom bar.

Price £713.10

Less 2 ½% mcd

All prices are exclusive of Vat.

Yours faithfully,

Stephen Boyce,  
Contracts Manager.

DESCRIPTION OF WORKS			
<b>JOINERYWORK</b>			
	Allow for supplying and installing new kitchen units to tea prep as per Howden Joiner Co, Clerkenwell Gloss White range, including plinths, corning, matching end panels. Include for all associated accessories to give a complete installation to kitchen. New units to comprise the following:		
A	Phase 1: 2nr W1000xD575mm sink base unit	ITEM	
B	Phase 1: 2nr W600xD575mm drawer-line base unit	ITEM	
C	Phase 2: 1nr W1000xD575mm sink base unit	ITEM	
D	Phase 2: 1nr W600xD575mm drawer-line base unit	ITEM	
	Allow for supplying and fitting new 39mm thick laminate worktop to new kitchen units. Worktop to comprise Howden Joinery Co, 38mm thick, black granite effect laminate worktop (WHT4160) . Allow for cutting of all holes in worktop as required for inset sink and pipework. Seal joints and abutment to walls, etc, in accordance with the manufacturers written instructions. Allow for installing worktop in continuous length with mitred joints (sealed) and for supplying and installing aluminium effect end caps at exposed edges.		
E	Phase 1: Print Room approx. 1.6 lin. m	ITEM	
F	Phase 1: Cleaners Store approx. 1.6 lin. m	ITEM	
G	Phase 2: approx. 1.6 lin. m	ITEM	
	Allow for supplying and fitting Altro Whiterock Splashback above all worktops, WHB's etc including wall returns, all to underside of windowsills, shelving etc. (max. 500mm high), allowing for cutting, fixing and hot welding of joints etc. Colour TBC.		
H	Phase 1 - Cleaners Store 2.2 lin.m	ITEM	
I	Phase 1 - Print Room 2.2 lin.m	ITEM	
J	Phase 2 - 2.2 lin.m	ITEM	
K	Allow for supplying and installing new roller window blinds by Rainbow Blinds or equal and approved; System 40 'Carnival China White Black Out Blinds' with manual side control chain fitted to comply with current blind safety regulations and sized to suit all external windows, colour white. Include for supplying and installing Louvolite tear drop bottom bar, and all other fixtures, fittings and accessories as may be required to give a full installation. Allow for supplying and installing MDF plate as required to receive new blinds.		
		SUM	713.10
	Amount of Joinerywork carried to Summary		£ 713.10